

May 12, 2014

COUNTY OF SAN MATEO
CRYSTAL SPRINGS REGIONAL TRAIL SOUTH OF DAM PROJECT
PROJECT NO. P9P09, FILE NO. E4911000
ADDENDUM NO.1

TO ALL PLAN HOLDERS:

The following **Addendum No. 1** to the above referenced project shall be included in the project plans and specifications.

1. Section 02830 Fencing has been modified such that black vinyl coating is required for two (2) chain-link vehicle gates and chain link fencing that fronts Skyline Blvd. at trail North entrance only and that chain link fence line posts shall be installed at every 10 feet where chain link fencing is required.

Replace page 118 with pages 118 A (rev) and 118 B (rev).

Please sign and return the attached "Receipt of Addendum No. 1 Form. The "Receipt of Addendum No. 1 Form MUST be received in this office either prior to the bid submittal or with the bid package submittal at no later than 2:30 P.M., Wednesday, May 14, 2014 or the bid will NOT be considered.

If you have any questions or require additional information, please contact Anthony Seto, Wency Ng, or Gil Tourel of our office at (650) 363-4100. They can also be reached by e-mail at:

aseto@smcgov.org
wng@smcgov.org
gtourel@smcgov.org

Very truly yours,



James C. Porter
Director of Public Works

JCP:AMS:GT:WN:as
f:\users\design\ddd\4911000\doc\addendum no.1\addendum no1.docx

Encl.- Receipt of Addendum No. 1 Form

cc: Ann M. Stillman, P.E., Deputy Director, Engineering and Resource Protection
Gil Tourel, P.E., Acting Principal Civil Engineer, Engineering and Construction
Wency Ng, P.E., Senior Civil Engineer, Project Development and Design
Anthony Seto, P.E., Associate Civil Engineer, Project Development and Design



To All Plan Holders
Crystal Springs Regional Trail South of Dam
Project No. P9P09, File No. E4911000

Re: Addendum No. 1

May 12, 2014

Page 2

COUNTY OF SAN MATEO
CRYSTAL SPRINGS REGIONAL TRAIL SOUTH OF DAM PROJECT
PROJECT NO. P9P09, FILE NO. E4911000

RECEIPT OF ADDENDUM NO. 1

I, _____, an
authorized representative for

_____, have received
Addendum No. 1 for the Crystal Springs Regional Trail South of Dam Project from an
authorized representative of the County of San Mateo, to be included in the Specifications
for the above referenced project.

This form must be signed and received in the offices of the County of San Mateo,
Department of Public Works ***either prior to the bid submittal or with the bid package
submittal at no later than 2:30 P.M., Wednesday, May 14, 2014.***

"Contractor"

(Print)

(Signature)

(Date)

3. Both top and bottom edges shall have non-knuckled selvages.
4. Fabric shall be hot dip galvanized after weaving to produce a zinc coated bare wire surface, ASTM A392, Class 2.
5. The wire in the completed fabric shall stand a tensile strength test of 75,000 pounds per square inch for No. 9 gauge, after galvanizing.
6. Fabric for chain link fencing and pedestrian gates shall be hot dip galvanized, except for chain link vehicle gates at trail North and South entrances and chain link fencing on either side of vehicle gate that fronts Skyline Blvd. at the trail North entrance, which shall be black vinyl coated.~~chain link gates shall be black vinyl coated.~~

B. Posts and Other Accessories

1. All posts and other appurtenances shall be galvanized in accordance with ASTM A123.
2. The weight of the zinc coating per square foot of actual surface shall average not less than 2.0 ounces, and no individual specimen shall show less than 1.8 ounces.
3. Posts, rails, frames, bars, and appurtenances for chain link fencing and pedestrian gates shall be hot dip galvanized, except for chain link vehicle gates at trail North and South entrances and chain link fencing on either side of vehicle gate that fronts Skyline Blvd. at the trail North entrance, which shall be black vinyl coated.~~chain link gates shall be black vinyl coated.~~

C. Line Posts

1. Schedule 40 commercial quality pipe having an outside diameter of 2.375 inches and a weight of 3.65 pounds per foot.
2. Line posts shall be installed at every 10 feet.

D. Corner, Brace, End and Pull Posts

1. Schedule 40 commercial quality pipe having an outside diameter of 2.875 inches and a weight of 5.79 pounds per foot.

E. Rails and Braces

1. Schedule 40 commercial quality pipe having an outside diameter of 1.660 inches and a weight of 2.270 pounds per foot.

F. Gate Posts:

1. Schedule 40 pipe having an outside diameter of 4.00 inches and a weight of 10.79 pounds per foot.

2. Gate posts shall be equipped with tops to exclude water.
- G. Fabric Connections
1. Tension bars shall be galvanized 1/4 inch x 3/4 inch steel.
 2. Pressed steel bands shall be galvanized 11 gauge.
 3. Ties shall be 9 gauges galvanized steel wire.
- H. Gate Frames
1. Frames shall be made of Schedule 40 commercial quality pipe having an outside diameter of 1.660 inches and a weight of 2.270 pounds per foot.